



#	Part Number	Component	Install Number	Qua
A	TP48T	Tree Posts, Topper Post & Deck-4’	TP24	1
B	TF36	Tree Fort Base, Posts, & Deck-3’	TF24	1
C	FA3001	Natures Nook	FA3001	1
D	FA3002	Boulder Bluff	FA3002	1
E	FA4306	Four Points Rope Climber - 4' to 4'	FA4306	1
F	FA4307	Valley Crossing Climber - 1' Rise	FA4303	1
G	FA4310	Crawl Tube - 0' Rise	FA4310	1
H	FA4701	Stream Slide - 3'	FA4701	1
I	FA4703	Stream Slide - 5'	FA4701	1
J	FA4902	Pine Tree Topper (TP) - 2' to 6'	FA4902	1
K	FA5103	Ladder Climber - 3'	FA5103	1
L	FA5118	Oak Slice - 4'	FA5117	1
M	FA5123	Log Pillar Climber - 3'	FA5123	1
N	FA5126	Rope Ladder - 4'	FA5126	1
O	VA3002	2-12 Age appropriate Name Plate	Installed	1
P	FA4900	Clubhouse Roof (TF) - 2' to 7'	FA4900	1
Q	FA4505L	Enclosure-15"-Left Hand	FA4505	7
R	FA4505R	Enclosure-15"-Right Hand	FA4505	7






All images and concepts are Copyright © 2025, Cre8Play, LLC - All rights reserved. Drawings are not to scale unless otherwise specified.



A 2 80014-WILDWOOD FOREST
PLAN VIEW




B 2 80014-WILDWOOD FOREST
ELEVATION

Installation Notes:

1- Paved surfaces, such as asphalt and concrete, are NOT acceptable for use under your structure.
2- It is the consumer's responsibility to check with local utilities prior to excavating footings for any underground utility lines that may exist within the installation area.
3- It is the consumer's responsibility to check local soil conditions and drainage within the site area. Inquire with local contractors for appropriate recommendations.
4- Assemble the entire structure BEFORE anchoring to concrete unless instructed in the individual component installation instructions.
5- Read the installation instructions provided prior to beginning construction.
6- The complete area under and around your play structure must be covered with impact attenuating material.


All images and concepts are Copyright © 2025, Cre8Play, LLC - All rights reserved. Drawings are not to scale unless otherwise specified.




A/3 CONCRETE FOOTERS
PLAN VIEW

A = 24" DIAMETER X 36" DEEP FOOTING (SUPPORT POST)
B = 18" DIAMETER X 24" DEEP FOOTING (SUPPORT POST)
C = 12" DIAMETER X 12" DEEP FOOTING (COMPONENT)
D = 12" DIAMETER X 24" DEEP FOOTING (COMPONENT)
E = 6" DEEP SLAB (SEE PAGE 6)
F = 4" DEEP SLAB (SEE PAGE 6)


All images and concepts are Copyright © 2025, Cre8Play, LLC - All rights reserved. Drawings are not to scale unless otherwise specified.



A CONCRETE FOOTING SECTION
SECTION-ELEVATION



B CONCRETE FOOTING SECTION
SECTION-ELEVATION




C CONCRETE FOOTING SECTION
SECTION-ELEVATION

Footing Notes:

1- Do not encase the bottom of the support post in concrete. Place the post directly on packed stone or brick.
2- The footings shown in this document are recommendations based on historical performance in average soil conditions.
Footing dimensions may be modified by owner based on actual soil conditions.
Before changing footing dimensions, we strongly recommend the footings be reviewed and approved by a registered engineer.
3- The base of the footings must be below the frost line.
4- Assemble the entire play structure before pouring concrete unless instructed to do so in the individual play component.

All images and concepts are Copyright © 2025, Cre8Play, LLC - All rights reserved. Drawings are not to scale unless otherwise specified.




D CONCRETE FOOTING SECTION
SECTION-ELEVATION

Footing Notes:


1- Do not encase the bottom of the support post in concrete. Place the post directly on packed stone or brick.
2- The footings shown in this document are recommendations based on historical performance in average soil conditions.
Footing dimensions may be modified by owner based on actual soil conditions.
Before changing footing dimensions, we strongly recommend the footings be reviewed and approved by a registered engineer.
3- The base of the footings must be below the frost line.
4- Assemble the entire play structure before pouring concrete unless instructed to do so in the individual play component.

All images and concepts are Copyright © 2025, Cre8Play, LLC - All rights reserved. Drawings are not to scale unless otherwise specified.

6” THICK CONCRETE SLAB
TYPICAL (VERIFY FOR LOCAL CONDITIONS)
MIN 3,500 PSI CONCRETE WITH
#4 (1/2”) REBAR GRID (16” OC)
CENTERED IN THE SLAB
-OR-
FIBER REINFORCED CONCRETE MIX
EQUIVALENT IN STRENGTH TO
MIN 3,500 PSI CONCRETE WITH
#4 (1/2”) REBAR GRID (16” OC)
CENTERED IN THE SLAB
(BY OTHERS)



E CONCRETE SLAB SECTION



F CONCRETE SLAB SECTION

4” thick concrete slab
typical (verify for local conditions).
MIN 3,500 PSI concrete with
6 x 6 wire mesh W2.9 x W2.9 W.W.F.
flat sheets, centered in the slab.
-OR-
Fiber reinforced concrete mix
equivalent in strength to
MIN 3,500 PSI concrete with
6 x 6 wire mesh W2.9 x W2.9 W.W.F.
flat sheets, centered in the slab.
(BY OTHERS)

Concrete Slab Notes:

1- Concrete slabs shown in this document are recommendations based on historical performance in average soil conditions. Footing dimensions may be modified by owner based on actual soil conditions. Before changing slab dimensions, we strongly recommend the slabs be reviewed and approved by a registered engineer.

3- Assemble the entire play structure before anchoring it to the concrete unless instructed to do so in the individual play component.

All images and concepts are Copyright © 2025, Cre8Play, LLC - All rights reserved. Drawings are not to scale unless otherwise specified.